GENG5505 (Sem1, 2023) - Major Group Project Marking Guide


Group Name:	Wednesday 5pm Group E		
Project Name:	Walyalup Civic Centre		
Tutorial class att	ended: Wednesday 5pm	(5)	0
Student Name	Aneena Sebastian	Student ID	23843815
Student Name	Marco Sham	Student ID	22707671
Student Name	Nikhil Sunil Kumar	Student ID	23664979
Student Name	Shubo Sun	Student ID	22179939
Student Name	Yazhen Tian	Student ID	22942152
Student Name	programme Cappi	Student ID	113.
Student Name		Student ID	

CONTENT ASSESSMENT CRITERIA

Marking	Very Poor		Fair		Good		Excellent	
Executive Summary (Maximum 1 page)								
Clarity & conciseness	0-1.5	2	2.5	3	3.5	4	5	
Executive Summary - Total								/5
Section A: Case study writing (Approx. 1,500 work	ds)							
Clarity & conciseness of project background	0	4	5	6	7	8	10	
Quality & relevance of research material (i.e. info/facts)	0	4	5	6	7	8	10	
Total Section A	V0	1111					3	/20
Section B: Case Study Analysis (Approx. 2,500 w	ords)							
Introduction (clarity of purpose & conciseness)	0-1.5	2	2.5	3	3.5	4	5	
Use & relevance of theories, models & frameworks	0	4	5	6	7	8	10	
Depth of analysis, clear & logical argument	0	4	5	6	7	8	10	
Total Section B	70	1111					101	/25
Section C: Recommendations to the case (Approx	. 2,000 wo	rds)						
Use & relevance of theories, models & frameworks	0	4	5	6	7	8	10	
Relevance & justification of recommendations	0-2.5	3	3.5	4	5	6	7.5	
Insight & synthesis, clear & logical argument	0-2.5	3	3.5	4	5	6	7.5	
Total Section C	Vo.						3	/25
Conclusion (Maximum 1 page)								
Logical summary	0-1.5	2	2.5	3	3.5	4	5	
Conclusion - Total	3 111		557.55					/5
Table of contents (compulsory), references & app	endices	, ,						
Appropriate table of contents, appendices & references	0-1.5	2	2.5	3	3.5	4	5	
Table of contents, references & appendices - Tota	al							/5
Group meetings (agenda & minutes)								
Relevance & consistency of issues & outcome	0	4	5	6	7	8	10	
Clarity, conciseness, team reflections and leadership	0-1.5	2	2.5	3	3.5	4	5	
Group meetings (agenda & minutes) - Total							3	/15

TOTAL	GROUP MARK /100	9/
	The second of th	

Additional comments (if required):				



WEDNESDAY 5PM GROUP E

ANEENA SEBASTIAN 23843815
MARCO SHAM 22707671
NIKHIL SUNIL KUMAR 23664979
SHUBO SUN 22179939
YAZHEN TIAN 22942152

Table of Contents

List of Abbreviations

Executive Summary

- 1. Section A: Case Study
 - 1.1 Introduction
 - 1.2 Project background
 - 1.3 Human Resources
 - 1.4 Key Stakeholder
 - 1.5 Issues/Competencies Relevant to Further Discussion
- 2. Section B: Case Study Analysis
 - 2.1 Introduction
 - 2.2 Conceptualisation
 - 2.21 Appropriate Site Management
 - 2.22 Economic Feasibility Management
 - 2.23 Scope Management
 - 2.3 Planning
 - 2.31 Stakeholder and Communication Management
 - 2.32 Procurement Management
 - 2.33 Risk Management
 - 2.4 Execution (Construction and Commissioning)
 - 2.41 Risk Management
 - 2.42 Procurement Management
 - 2.43 Scope management
 - 2.5 Finalisation
 - 2.5.1 Risk management
- 3. Section C: Recommendations
 - 3.1 Introduction
 - 3.2 Stakeholder and Communication Management
 - 3.21 Conduct a Stakeholder Analysis

- 3.22 Improve the Communication Plan
- 3.23 Mapping Stakeholders Power and Interests
- 3.3 Risk Management
- 3.4 Procurement Management
- 3.5 Time Management
- 3.6 Cost Management
- 3.7 Scope Management
- 4. Conclusion
- 5. References
- 6. Agenda and Meeting Minutes
 - **6.1 Team Meeting 1: 6 March 2023**
 - **6.2 Team Meeting 2: 9 March 2023**
 - **6.3 Team Meeting 3: 15 March 2023**
 - 6.4 Team Meeting 4: 20 March 2023
 - 6.5 Team Meeting 5: 27 March 2023
 - 6.6 Team Meeting 6: 9 April 2023
- 7. Team Reflections
- 8. Appendices

Appendices 1 WCC Plans with Legends

Appendices 2 WCC Project Site Plan

Appendices 3 Timeline of WCC Project

Appendices 4 Risk Management Matrix

Appendices 5 Work Breakdown Structure

Appendices 6 Evidence of Email Correspondence with KHA Project

Manager

Appendices 7 Final Cost of the WCC Project

Appendices 8 Interview Questions

Report Section	Recommended	Actual
Executive summary	-	406
Section A: Case Study	1,500 ± 75	1447
Section B: Case Study Analysis	2,500 ± 125	2539
Section C: Recommendations	2,000 ± 100	2007
Conclusion	-	248
Total	6,000 ± 300	5993

List of Abbreviations

Abbreviations	Full Name	
CEO	Chief Executive Officer	
EOI	Expression of Interest	
KHA	KHA Kerry Hill Architects	
LED	Light Emitting Diode	
OSH	Occupational Safety and Health	
PBA	Project Bank Account	
PCG	Project Control Group	
PMBOK	Project Management Body of Knowledge	
PSG	Partnership Steering Group	
RACI	Responsible Hence the Acronym	
RFT	Request For Tender	
TBL	Heritage Impact Statement	
WBS	Work Breakdown Structure	
WCC	Walyalup Civic Centre	

Executive Summary

The Walyalup Civic Centre (WCC) construction project is part of the Kings Square Renewal Project approved by the Fremantle Council. This report provides a detailed analysis of the WCC project management. The project was designed by Kerry Hill Architects and managed by Pindan Construction in the initial phases and later by the CDI Group. The WCC was designed to reduce the operational and maintenance costs and to improve the efficiency of the old administration building but without affecting the integrity of the nearby cultural heritage sites. The newly constructed building has an award-winning design which aims to provide sustainability, economic integrity, and social benefits to the community.

We have done a thorough investigation on the project and identified several issues regarding its project management and suggested several recommendations that could have helped mitigate those issues. The critical analysis and recommendations were made with reference to the project management concepts and frameworks. In section A, we provide the project background with a major focus on its justification, overall budget, key stakeholders and several issues and competencies.

In Section B we have done the critical analysis of the project management. Initially all the separate phases of the project lifecycle were defined and then we identified all the effectiveness and shortcomings of the management with reference to Project Management Body of Knowledge (PMBOK) competencies. The project started off with the conceptualisation phase and during this phase an appropriate site was identified for the project and studies were carried out to understand its economic feasibility. It was followed by the Planning phase in which we addressed the importance of stakeholder management. A key issue in the planning phase was not accurately assessing the financial risk, which resulted in the project going over budget. Execution of the project had some issues that led to fire pump failure and flooding

inside the building. The finalisation phase addressed drawbacks of Work Breakdown Structure and how they tried to solve the issues identified in planning and execution stage.

While some problems were handled correctly, others may have been solved by using better approaches. Section C presents these recommendations or changes that could be applied to the project lifecycle components from appropriate theories and conceptual frameworks from the course. Although the WCC project became successful in providing a sustainable and community-focused infrastructure, even better outcomes have been possible with stronger project management strategies in the areas of stakeholder, communication, time, cost, procurement management.

1 Section A: Case Study

1.1 Introduction

The Walyalup Civic Centre (WCC) was designed by Kerry Hill Architects (KHA) and is located in Walyalup Koort (formerly Kings Square) - the central square in Fremantle, Western Australia (*Figure 1*). The project was physically completed at the end of October 2021 and subsequently opened to the public with services commencing on 22 November 2021. The WCC project includes offices for the Fremantle City Council, the Fremantle Library and a visitor centre with meeting rooms, art galleries and exhibition spaces for public use. The spaces are intended to provide cultural, social and recreational activities for local residents and visitors, as well as a venue for various meetings and events for Fremantle City Council and other organisations. Importantly, the design of the WCC embraces not only the importance of the site as a historic town centre, but also its thousands of years of indigenous history. The WCC project is one of the largest infrastructure projects in Fremantle's history and is one of the most iconic cultural and arts centres in the Perth region.




Figure 1 - Location of the Walyalup Civic Centre

1.2 WCC Project & Context

Walyalup Koort, where the WCC project is located, has been the civic and geographical centre of Fremantle since the town hall was built in the 1880s. Walyalup is the traditional Aboriginal name for Fremantle, while Koort means heart. In recent years, its status as the centre of Fremantle's central business district has been declining. The urban design strategy for King's Square was to assess the function and form of the square and the surrounding area and to develop a strategy to revitalise its position as the true urban centre of Fremantle, Walyalup Koort is a space that has been extensively used by the community for market and public events, entertainment and council business. The urban design strategy sees the square as a civic centre and a key business hub for the regeneration of Fremantle. Walyalup Koort responds and connects to everything Fremantle has to offer.




Figure 2 - Kings Square in 1971



Figure 3 - Walyalup Koort (formerly Kings Square) in 2021

The WCC is essentially a part of the 230 million AUD Kings Square renewal project. It all started off in 2004 when the Fremantle council developed the civic area redevelopment project after they found out that the that the old administration building was inefficient from both an environmental and operating cost perspective. The building was suffering from suffering from concrete cancer, severe asbestos contamination and it was also unable to meet the legal disability requirements and all these issues meant that it needed large amounts of money annually for the maintenance costs (City of Fremantle n.d.).

The Kings Square renewal project's main aim was to redevelop the region within the Kings Square which included the city owned buildings as well as privately owned Myer building. However, the project was put on a hold until 2011 when the council was forced to look into the subject as there was a considerable decline in the economy of Fremantle. The situation became even worse when Hoyts cinemas one of the major tenants in the Qeensgate complex decided not to renew their lease in 2012 due to the failing structural standards of the building and Myer, one of the large retail stores was forced to close down their store in 2013 due to a decline in the importance of department stores. Therefore, to rebuild the economy of Fremantle, the council was forced to establish new economic development and planning strategies to attract more investments which in turn will generate jobs and will encourage people to come and work in the region. The redevelopment of the Kings Square and upgrading the public spaces surrounding the square was one of the major steps in achieving that. And to keep the project running the Fremantle council signed a commercial agreement with Sirona Capital to fund the project which includes the redevelopment of the old Myer building and Qeensgate which formed a broader part of the Kings Square. However, Sirona Capital would not have invested in the project unless and until Fremantle city would commit to redeveloping the civic and community facilities in the square.

Finally, a total budget of 41.3 million AUD was approved for rebuilding the civic centre but to allow the installation of a new fire protection system and include several

other improvements the budget amount was further increased to 42.6 million AUD. The approval for a new civic centre meant that it would get new looks, with better functioning, less maintenance costs and it will also reduce the need for costly extensions and technology upgrades in the future (City of Fremantle n.d.).

1.3 Human Resources

The PCG is made up of at least one member from each partner organisation and is designed to jointly lead and oversee the implementation of a project or partnership. The PSG for the WCC project is made up of members of the City of Fremantle, KHA and Pindan teams. Each member of the PSC provides a letter of support before the project Each member of the PSC provides a letter of support prior to the start of the project. The PSC helps to ensure that the project or partnership runs smoothly and ultimately achieves its objectives.

In parallel, the city proposed an internal Project Control Group (PCG) process, outsourced project management, a robust governance framework and dedicated (external) development management resources to support the project.

1.4 Key Stakeholder

"Stakeholders can come from all levels of the organization, and if they are involved in your project, they are important" (Martins, 2023). WCC as a public project has a very broad stakeholder. The public areas of the WCC project can be used throughout the week and during the day, from early morning to late evening to attract visitors from a variety of key stakeholders, including elementary and high school children, university students, families, empty nesters, retirees, day trippers and tourists. The data shows (Table 1) that families and young adults are the most popular key stakeholders for WCC projects. Stakeholders in the conference room, on the other hand, mainly include government, companies and many community groups. Table 2 shows the main stakeholders involved in the WCC project.




Table 1 - Key Stakeholders in Public Areas

Architectural design	Kerry Hill Architects
	 Architects based in Singapore and Western
	Australia (Vivian, 2023)
Consultants	> Acoustic Consultant
	 Marshall Day Acoustics
	Building surveyor
	 Resolve Group
	> Electrical engineering, vertical transport
	 BEST Consultants
	Civil and fire consultant
	- Stantec Australia
	> Façade engineer
	 Inhabit Group
	Heritage Consultant
	 Hocking Heritage
	> Lighting commissioning
	 Firefly Point of View
	> Traffic Consultant
	 Edge Transport Solution
	> Waste Consultant

	_	Encycle Consulting
Government Agencies	>	City of Fremantle
Service	>	Customers
	_	The library user
	>	Renter
	-	The meeting room renter
Contractor	>	Pindan Constructions
	>	CDI Group
Other	>	property owners
	>	Community groups
	> Fremantle business community	
	> Department of Communities (Mart	
	2023)	
	>	General public
	>	City of Fremantle Elected Members
	>	Fremantle Council
	_	Concerning the finances of the Walyalup
	Civic Ce	ntre (Loopers, 2020)

Table 2 - Key Stakeholders

1.5 Issues/Competencies Relevant to Further Discussion

Throughout the lifespan of the WCC project, unexpected and unforecastable problems had arisen such as the liquidation Pindan, the main contractor with the construction of the civic centre and the introduction of the Covid lockdowns restrictions. These are problems that required quick action and a better understanding of the risk factors to determine the most effective control and treatment strategy.

At the beginning of the project, an audit and risk management committee were formed and had discussions of possible problems arising for the duration of the project. The discussion is all documented in a risk register summary. Which has outlined the risk event, the estimation of the possibility of the risk occurring, an estimation of the importance of the risk and a mitigation strategy. These assessments are then assigned to individuals responsible for the risk with target date to action the mitigation strategy. The outcomes from the mitigation and evidence supporting the outcome to produce must be documented after which produces accountability.

COVID-19 has impacted Pindan's supply chain due to delays in importing some materials, but the team has worked together very well to reschedule the work and ensure that the building is completed on time (Centre, 2022). The city maintenance workers protested the council to remove clause 19.3.2 of the contract which allows the council to force workers into unpaid leave if they do not have enough holidays to get them through a partial shutdown. The deputy mayor Andrew Sullivan handled the situation by explaining the rules and by pointing out that the clause has been in place since 2011 (Herald, 2021).

2 Section B: Case Study Analysis

2.1 Introduction

The lifecycle of the WCC project consists of four main phases. These are the conceptualisation, planning, execution, and finalisation phase. The significance of analyzing the project lifecycle is to help project managers understand the phases from inception to completion, and the work and resources required for each phase. This helps managers to plan and budget appropriately to ensure that projects are completed on time and remain efficient and effective throughout the process. This section unpacks the project-related deficiencies presented in Section A through the four stages of the project lifecycle, analyses the root causes behind these events, and discusses their impact on the project.

2.2 Conceptualization

2.21 Appropriate Site Management

As one of the most important projects in the Kings Square Renewal project, the WWC project is highly valued by the City of Fremantle. Although there are sufficient arguments to demonstrate the WWC project's rationality, it is still necessary to conduct research and protection on issues such as the environment, cultural heritage, traffic, and land use, before the establishment of the project scope.

Fremantle has very distinctive cultural characteristics and a lot of historical background, so this brings up the problem of whether such a large area of construction will destroy the historical heritage and the original environment of this region, or whether it will affect the life and migration of some endangered animals (City of Fremantle, CEO Application Pack, 2022).

Doing research on the local historical heritage and environment and consulting relevant departments can also be a problem, which definitely takes a lot of time and money, especially under financial pressure. However, good communication with these stakeholders can prove the reasonability of the site selection, and it is a good foundation for follow-up construction work.

2.22 Economic Feasibility Management

Economic feasibility is an important research indicator of whether this project can be approved. Energy consumption is a big problem for a building of this size. If the project team just relies on traditional power supply and energy usage, more wires and pipes are required and water a lot of energy, but using LED and solar energy systems will greatly save operating costs (Tverberg, 2016). WWC project should be under the assessment of the reasonably economic feasibility because of the high operating cost of traditional energy using.

2.23 Scope Management

As the most important guiding direction of the entire project, scope management clearly gives the scope of a project at the beginning of the project (PMBOK, 2013). To meet the needs of people at different stages, WWC project's initial design needs to include government offices, conference rooms that can be rented, public libraries and entertainment facilities, etc. This makes the approval process of the entire project complex and detailed. The advantage is that the scope of the project is better controlled to prevent excessive sprawl. However, a few problems arose that affected the initially set schedule and budget targets, which resulted in changes in the scope.



Figure 4 – WCC Project Concept Drawing

Although the Fremantle government wanted to keep the project going, there were financial disputes during the construction process. Potential problems need to be anticipated in the conceptual stage and corresponding measures must be proposed (Hartley, 2014). However, from the project team's perspective at the time, such potential problems within the scope were unpredictable.

2.3 Planning

After the concept phase, the schedule and work of the whole project is planned. The project team define and assign all the objectives, resources and timelines for the project and other administrative requirements.

2.31 Stakeholder and Communication Management

Stakeholder and communication management are crucial aspects of the planning phase for a WCC project. During this stage, it is necessary to identify, validate, and understand the needs, expectations, and interests of project stakeholders. This approach ensures that the project caters to the needs and expectations of all involved parties, while also helping to prevent conflicts and issues from arising. The WCC project, a public initiative aimed at the general population, involves a diverse and complex array of stakeholders. To accommodate this, the planning stage should address the needs of various stakeholders, considering the unique circumstances of each population group and usage environment.

The primary shortcoming of the WCC project in the planning phase lies in its lack of transparency toward stakeholders. This problem can be attributed to the insufficient identification and analysis of stakeholders, who are diverse in nature. Neglecting to thoroughly identify and analyze all key stakeholders during the planning stage may lead to unmet needs during project implementation. Additionally, it could give rise to unforeseen issues or needs. These factors might contribute to potential problems or conflicts, causing delays, increased costs, or unattained project objectives—ultimately

affecting the project's overall quality and success.

2.32 Procurement Management

Project procurement planning involves decisions made to acquire necessary resources. An assessment is required to determine if the needs are 'best satisfied in the open market.' Procurement management can add value to the project, and planning for procurement is necessary for the project's supply chain strategy (Hartley, 2018).

The city's assessment for choosing a suitable contractor for the WCC was primarily influenced by the cost quoted by the contractor. Inadequate evaluation during the tendering process resulted in a poor choice of contractor. In this case study, Pindan quoted 10 million AUD less than the next contractor (HERALD, Y., 2021). The choice of a fixed-price contract led to significant quality control issues in the project.

The contract's poor quality was also an issue during the planning phase, as it did not accommodate changing project conditions, such as the Covid-19 pandemic and Pindan's liquidation.

Covid-19 forced contractors and suppliers to increase costs and delivery timeframes, placing pressure on work programs and deliveries (Fremantle, 2022). To address this issue, the project team actively liaised with contractors and suppliers, rechecking programs or delivery lead times during the execution phase. This effectively extended the time and cost of the execution phase, resulting in delays to the finalization phase. The pandemic's problems could have been mitigated during the planning phase with better procurement management. More precise contracts would have resulted in fewer delays.

The Pindan liquidation event posed a risk, as the site project team from Pindan had significant knowledge and contractor relationship management in the WCC project. Losing the site project team could have led to considerable risks, costs, and delays

(Fremantle, 2022). The city mitigated this by immediately engaging key Pindan site project team members; however, staff retention remained a risk. Furthermore, materials left by Pindan after the liquidation were untouched due to uncertainties of ownership, causing time delays in the execution phase (Fremantle, 2022). Like with Covid-19, procurement management during the planning phase could have reduced the impact, uncertainties, and delays caused by the liquidation event.

2.33 Risk Management

Risk management during the planning phase allows the project management team to identify most project aspects before the project commences. The city created a risk assessment matrix (*Appendix 4*) in the business plan, identifying several issues:

1) Lack of detailed mitigation strategy:

In the risk mitigation matrix, the risks and mitigation strategies were not defined in detail, resulting in poor execution of mitigation strategies. Poorly defined/planned mitigation strategies are equivalent to having no plan at all, which will result in project delays and increased costs. For instance, unsupervised work by Pindan led to quality issues where welding was misaligned, and there was no proper mitigation strategy for this issue, resulting in lengthy delays for Pindan to correct their mistakes (Loopers, 2021).

2) Identification of only simple risks:

The project team identified and mapped risks but failed to be more comprehensive with risk identification during the planning stage. This resulted in unidentified risks being automatically excluded from further analysis. The project team also failed to consider that risks evolve throughout the project's lifecycle. As a result, no instant approaches could be actioned to address the evolving risks. The lack of risk identification was evident with the liquidation of the main contractor. The loosely defined risk resulted in no specific mitigations planned before the project's execution phase. This issue halted the project as the city

struggled to maintain construction operations.

3) Poor execution of mitigation strategies:

When Pindan faced liquidation, the city had already made strong provisions in their contract with Pindan. This allowed the city to engage with all existing novation deed contractors, who agreed to complete the remaining scope of work (Fremantle, 2021). The issue was that the planning team failed to ensure that the contract fully protected the city from budget repercussions and did not make explicit decisions to commit more resources or budget before the execution phase. Consequently, when the city had to change the main contractor during the project, it resulted in increased project costs and an extended execution phase.

2.4 Executions

2.41 Risk Management

The WCC in Fremantle reached practical completion in late October 2021 and opened to the public for service delivery on November 22, 2021. However, during construction, the building experienced issues, including a flooding incident on November 25th caused by a fire pump failure in the lower ground plant room area (Fremantle, 2022). The problem originated from a valve failure in the basement fire pump plant room, resulting in the room flooding. Water damage was confined to the fire pump room, control panels, and a small area of carpet tiles in the library's rear section. The consequences were severe, necessitating the closure of the facility for employees and the public until December 6, 2021. Rectification work was completed, and the building resumed its original function on December 20, 2021 (Fremantle, 2021). This failure resulted from inadequate implementation of plans established during the planning phase and insufficient fire management measures. The incident could have caused damage to the building's furnishings and equipment.



Figure 5 - WCC Project Under Construction

2.42 Procurement Management

During the construction of the building, there were serious concerns regarding violations of the Occupational Health and Safety Act and substandard welding practices. John Dowson, the president of the Fremantle Society, reported that the structural steel frame forming the canopy showed significant sagging, and many bolts failed to align with their intended positions as per the engineering plan. Although initially denying knowledge of these issues, Pindan later admitted to using a mobile crane to lift the sagging canopy structure into its correct position and welding the structure (Loopers, 2021). Furthermore, concerns arose about the rusted surface on the steel framing that supports the alloy façade on the complex's eastern side. Visible rust on the steel framing (Robinson, 2022) may require annual repainting of the frame.

Additional concerns stemmed from the steel being manufactured and fabricated in Vietnam before being imported to Australia. This choice raises questions about the poor-quality welding and camber resulting from the overseas fabrication process. The decision to use Vietnamese steel over Australian steel contradicts the city council's sustainability claims (Loopers, 2021). The WCC project operated under a fixed-price contract model. Although these contracts necessitate a detailed scope or requirements,

internal management problems at Pindan, along with inflation in material costs due to supply chain disruptions caused by the Covid-19 pandemic, led to changes in the project scope during its execution. These changes resulted in the quality issues mentioned above.

2.43 Scope Management

The execution phase also encountered scope management challenges. A lack of detail in the specifications caused confusion regarding contractor responsibilities, leading to incomplete or neglected intended features during construction. Smaller deliverables were not prioritized during construction, particularly when the pandemic caused a shift in organizational culture, enabling scope creep. The combination of scope creep and insufficient detail led to the elimination of agreed-upon aspects of the project due to budget constraints. For example, Ryan from KHA stated in an interview that a miniature pond was initially planned for construction next to the library area. However, due to increased material and labor costs resulting from the pandemic, the pond was abandoned in favor of a more cost-effective alternative, such as a study area.

2.5 Finalisation

The finalisation phase is essentially when the project is being handed over to the client after its completion. During the initial stages of this phase all the contracts are closed, and the resources are either disposed of or reassigned. Final detailed reports are prepared and presented before the project administration is dismissed.

Since Fremantle council wanted to open the WCC to the public before Christmas the Finalisation phase was executed in stages and it started when the construction work was just partially completed. In late October 2021, the building was partially completed and after running preliminary tests the building was opened to the staff and public on 22 November 2021.

The City of Fremantle (the client) was following a Work Breakdown Structure (WBS) for managing the costs associated with the delivery and reconciliation of the project. Since the entire project was nearly 3 years long and involved the contribution of different trades, the City had a staggered retention payment method. This ensured that the first 2.5% would be released once the contractor completes the work, and the second 2.5% would only be released after a period of 12 months, which is considered the defects liability stage (City of Fremantle 2022a). By early June 2022, most of the contractors got their final account, and they had received their first 2.5% retention payments. However, they would get the second 2.5% only after the 12-month defect liability stage has been served (City of Fremantle 2022b).

2.5.1 Risk management

The WCC was opened to the public on 22 November 2021. However, in just 3 days, the lower plant area of the building was flooded and was forced into a shutdown to complete the rectification works. The flooding event had significant financial implications and the estimated total cost for the maintenance works was around 175,000 AUD. The mishap was due to a malfunctioning valve in the fire pump plant room situated in the basement room of the building. This caused the entire room to flood and inflicted severe damage to the control panels placed inside the room and since the library is also situated near the basement, the water leaked into the room and damaged several carpet tiles installed.

This event was a result of poor risk management by the project management as they failed to identify the risk and assess its implications. In the initial approved design and budget, there was no plan to install a fire pump system, the decision to install the pump system was taken later commissioned for an additional amount of 1.3 million AUD. This fast-tracked decision is one of the major underlying reasons that led to the mishap because in the small time frame the project management group did not have adequate time to identify and assess the risks related with its installation. Additionally, after all the delays caused during the project, the city of Fremantle

wanted to open the building to the public and staff before the 2021 Christmas season, so the project management team was forced to open it when it was just partially completed. This decision meant that the management team had to do all the preliminary tests and quality checks while the management team had to do all the preliminary tests and quality checks within a small-time frame.

3 Section C: Recommendations

3.1 Introduction

Section C of this report will present some key recommendations for the life cycle of this project, designed to help address the issues facing the project more effectively. These recommendations will apply the appropriate conceptual framework and theory to address the challenges identified in the previous section. These recommendations should be carefully considered and implemented in order to improve the final outcome of the project.

3.2 Stakeholder and Communication Management

3.21 Conduct a Stakeholder Analysis

As mentioned before, a Stakeholder analysis is to have a better risk management and grasp the development direction of WCC. For this reason, city of Fremantle has recorded all the key stakeholder, such as, designer, builder, the social community, etc. However, to make WCC have a sustained appeal to the public, the subsequent analysis of the key stakeholder should focus on "the users of WCC". It is strongly recommended to set up the specific team to investigate at different levels of society, such as the student stage, working stage, retirement stage, etc. Especially in this network-developed society, maintaining the use of traditional libraries and the rental of meeting rooms can maintain the continuous mark attractiveness to key stakeholders in the competition with the online model, which requires managers to construct a complete stakeholder analysis.

3.22 Improve the Communication Plan

There is an argument between South Fremantle Councillor Marija Vujcic and the City of Fremantle administration about the real cost for WCC (Loopers, 2022), which approves that there are still have some problems on the communication. It is

recommended that the city of Fremantle should create a more effective and transparent communication platform so that the government, builders and citizens (or Fremantle ratepayers), the three most important stakeholders will have a better communication. On this platform, citizens can know where the money is spent for this project, contractors can make new announcements if some facilities are being repaired or expanded, the project leader can also know more opinions and needs from stakeholders and strive to reach agreements and resolve conflicts with all stakeholders through such a platform.

3.23 Mapping Stakeholders Power and Interests

Mapping a stakeholder power and interest matrix (Figure 6) is the most beneficial way to meet stakeholders' expectations and to effectively reduce future conflicts with stakeholders.



Figure 6- Power and Interest Matrix

This matrix will more clearly show the position of stakeholders, so that managers can make corresponding targeted strategies for different stakeholders (Hartley, 2014), therefore, the more important things from the stakeholders get prioritized.

	Stakeholders				
TASK	City of Fremantle KAH Pindan Business				
				Community	
Constraction	A	С	R	I	
Design	A	R	С	I	

Land Asset	A	R	C	I
Planning				
Vendor	R	C	A	I

Table 3 - RACI Matrix Legend (Hartley, 2018)

Index	Responsibility	Description
R	Responsible	Activity owner
A	Approve	required with approving the undertaken activity
C	Consult	required to be consulted with during or after activity
I	Inform	required to be informed of activity

Table 4 – Definition for RACI

The RACI matrix portrayed above as table 3 is a tool that assists with defining the responsibilities of key stakeholders. The matrix appoints required actions to stakeholders, actions consist of requiring the stakeholder to approve, consult, inform or be responsible hence the acronym (RACI) for certain tasks (portrayed above). The RACI matrix ensures that the stakeholders agree to abide by the recorded activities and also allows them to understand their responsibilities regarding the task. If RACI was deployed in the WCC project, corner cuttings and quality control of the construction by Pindan would have been avoided. Furthermore, the matrix would be used as a reference to see which party in the project is responsible if an issue has occurred.

3.3 Risk Management

One of the major risks that occurred in the project was the flooding that occurred due to a faulty valve in the fire pump system. As mentioned earlier it was a result of the above-mentioned reasons have played a major role in the mishap that occurred on the eve of 25 November 2021, just 3 days after the building was opened.

The project management team could have prevented or at least mitigated the impact of such an event if they had efficiently followed a six-step model which involves:

- Developing a proper plan for risk management with a proper structure. And it should be done with direct and continuous involvement of the key stakeholders.
- Identification of the risks involved by involving all the key stakeholders, the project manager, the experts and clients. The risk that had occurred in this project is because the management team were unable to identify a "known unknown" type of risk event, because in a fire pump installation the chance of flooding is really high, but we cannot predict when that is going to happen.
- Perform a qualitative and quantitative risk analysis to assess the probability, impact and priority of the risk. For this the project manager could have generated a risk matrix which could have given the stakeholders the chance to understand the type of risk, its probability, impact and even its priority.
- Planning proper Risk response strategies with the help of risk response matrix.




Figure 7 - Risk Response Matrix

- Monitor continuously for the effectiveness of risk processes and
- Continuously evaluate the effectiveness of the risk processes in order to control it.

Following all these steps could have helped them identify the risk in the initial stages and given them sufficient time to conduct the necessary quality check tests to confirm the proper functioning of the fire pump system. Additionally, they could have also installed some small bunds or water drainage systems in the room to mitigate the impact of any such incident in the far future.

3.4 Procurement Management

We recommend several methods to be taken to improve procurement management with following methods as suggested:

1) Regular performance reviews.

Performance reviews are specified in the contract but often is poorly enforced and communicated. Regular performance reviews provide the benefits of allowing the comparison of performance against plan, accurately and timely reporting of problems and enhances the timely implementation of any corrective action required (Hartley, 2018). Performance reviews are clearly not reinforced in the WCC project as analysed in section 2.42, where the city and Pindan faced scrutiny and unpleased the stakeholders through occupational Safety and Health (OSH) violations and underperforming materials which was not corrected in a timely manner. We recommended that project as big as WCC with many stakeholders should perform performance reviews more occasionally than standard practice which allows the constant monitoring of the contractor. The constant monitoring of the contractor ensures that the contractor enforces and deliver quality specified in the contract therefore, preventing contractors cutting corners.

2) Preparation of more concise and detailed contract documentation which ensures performance by participating parties met expectations.

Contracts are the underlying legal framework for the project. It is legally binding and will need to be appreciated, enforced and complied with by the organisation, project manager, key stakeholders and team members (Hartley, 2018). We recommend that the contract should be subdivided into smaller sections that scrutinise each part of the project. By placing more details into each part of the project it ensures that problems caused by contractors are more easily to handle and project would be easier to control. Time delaying events discussed in section 2.42 would have been easier to mitigate and handle by including possible events that negatively impact the project into the contract which will make the contractor or responsible party liable to the damages and costs.

3.5 Time Management

As mentioned in Section B, the time management issues resulted in unforeseen additional costs in the project budget, with each cost increasing due to the extension of time. Figure 4 shows an example of a graphical WBS that captures the project

activities for a property refurbishment project. We recommend that WCC projects create a similar WBS to capture project activities, either in the form of a table or a graph, before creating a network diagram and Gantt chart (Hartley, 2018).




Figure 8 - WSB WCC Project Network Diagram

These charts can provide a clear visual representation of the events that must occur sequentially throughout the lifecycle of a WCC project. They can also be used to test the logic and accuracy of the WBS and help to identify the critical path and predict the time required for each task, as well as any activities that may cause bottlenecks. These tests will increase the flexibility of the project and help to avoid delays.

The critical path for the WCC project is the longest path in the overall schedule. By conducting a critical path analysis of the project, we identified the activities to install and test the smart technology as key project activities. Some aspects of incompleteness could be mitigated by conducting a critical path analysis. It is recommended that KHA adopt a similar rigorous critical path analysis methodology for future projects.

The project experienced delays due to a new builder but the project end date was not adjusted accordingly. For this issue, we recommend re-evaluating the project's time schedule. Consider the impact of the change of builder on the project schedule and

re-evaluate the project's time plan. You may need to adjust the duration or period of each task to reflect the impact of project delays. If necessary, consider additional resources or timely adjustments to the project plan to expedite the project.

3.6 Cost Management

Cost management is the process of planning, estimating, budgeting, financing, funding, managing, and controlling costs to enable the project to be completed within budget (PMBOK, 2013).

Budget management was an issue in the project. As discussed in Section 2.32, liquidation of Pindan, supply chain issues due to Covid-19, scope changes during the project execution resulted in increase in budget. The City of Fremantle failed in delivering on its financial risk management strategy, where it clearly stated that all cost over-runs would be managed via a fixed price contract for the building construction, where the contractor would be liable for cost overruns (Loopers, 2020).

While creating a financial plan, it is important to consider several factors such as the source of funds, reporting formats, internal finance protocols, and accounting system. It is also crucial to identify percentage variation thresholds that may require action and have provisions for contingency funding. Approval procedures must be established and a certain level of accuracy in determining cost estimates should be maintained. Known units of measurement should be defined for each resource, and the required degree of precision should be specified. Additionally, a performance measurement technique must be selected (Hartley, 2018).

To finalize the budget for a project, various cost estimation techniques can be employed. These techniques include;

- Pre-determined estimates that are announced by senior management in isolation from other variables.
 - Expert judgment that relies on specialized knowledge or training.

- Analogous estimates derived from historical data of similar activities.
- Group decision-making through interactive sessions with team members.
 - Unit rates based on accurately defined discrete units of work.
- Published commercial data obtained through subscription services providing access to current costs of labour, materials, and equipment.
- Parametric estimating that combines historical information and project variables statistically (such as per square meter, per litre, per hour, etc.).
- Value engineering, which focuses on reducing project costs, saving time, increasing profits, and improving quality.
- Life-cycle costing, which considers both the creation costs of the project and its usefulness over time.
- Vendor bid analysis, which involves market research and invitations such as expression of interest (EOI) and request for tender (RFT).
- Reserve analysis which considers schedule uncertainty and risk by allocating a contingency reserve for 'known unknowns'.
- Three-point estimation, a technique that calculates an expected duration range based on optimistic, pessimistic, and most likely estimates (Hartley, 2018).

•

3.7 Scope Management

As section B mentioned, the scope has changed due to the potential impact on scope and accurate estimates of the budget. When face to the potential impact on scope changes, such as the large-scale epidemic caused the progress of the project to stagnate, it is recommended that if Pindan finds that its operating capacity has been maxed out, it should cooperate with other construction companies or partners to jointly carry out projects and share resources and experience to improve efficiency and reduce costs.

4 Conclusion

WWC project is a successful and inventive renewal project, which ingeniously combines modernist architectural style and historic architecture style. While protecting the local historical heritage of Fremantle, it provides a current and comprehensive public place for the government and citizens and other stakeholders. It solves the problem of insufficient operating capacity of the original Fremantle library and traffic issues in the previous narrow land place. WWC is a milestone for the entire king square renewal project, which makes the king square a fully functional public service area. It not only provides more jobs for the society, but also attracts more investment to drive the economic development of the entire region.

Even though the project was a success, there are issues throughout the project that made it more difficult than it should have been to achieve the same outcome. These issues were identified, and we have provided recommendations from the perspective of the city's management team to mitigate these issues. The main issues identified was liquidation of the main contractor which resulted in expensive delays, usage of underperforming materials and contractors, lack of quality control resulting in an underperforming product, insufficient engagement to stakeholder resulting in negative perceptions to the project and incomplete time management planning resulting delays of the execution and finalisation phases. Our recommendation to mitigate these issues are preparation of high-quality contracts, inclusion of more effect cost estimation techniques, utilisation of a WBS, take inconsideration of critical path of project and risk breakdown structure.

5 References

CENTRE, W. C. (2022). *Walyalup Koort renewal project achieves its goal*. [Online]. City of Fremantle. Available:

https://www.fremantle.wa.gov.au/news-and-media/walyalup-koort-renewal-project-ac hieves-its-goal [Accessed 13 March 2023].

City of Fremantle. (2022). *Agenda – Audit and Risk Management Committee*. [Online]. Available:

https://www.fremantle.wa.gov.au/sites/default/files/Agenda%20-%20ARMC%20-%20015%20June%202022%20%28ID%205423815%29.pdf [Accessed 17 March 2023].

City of Fremantle. (2022). *Meeting Attachments – Audit and Risk Management Committee*. [Online]. Available:

https://www.fremantle.wa.gov.au/sites/default/files/Meeting%20attachments%20-%20 ARMC%20-%2015%20June%202022%20%28ID%205423818%29.pdf [Accessed 17 March 2023].

City of Fremantle. (2012). *Kings Square Project Business Plan*. [Online]. Available: https://adelecarles.com/wp-content/uploads/2021/09/2012-11-Kings-Square-Business-Plan.pdf [Accessed 20 March 2023].

City of Fremantle n.d. (2021). Why is the city investing in Walyalup Koort? [online]. Available at: https://www.fremantle.wa.gov.au/why-city-investing-walyalup-koort. [Accessed 20 March 2023].

FREMANTLE, C. O. (2022). Agenda Audit and Risk Management Committee.

FREMANTLE, C. O. (2021). Walyalup Civic Centre Update. [Online]. Walyalup

Koort: City of Fremantle. Available:

http://www.walyalupkoort.com/news-and-updates/walyalup-civic-centre-update [Accessed 09 April 2023].

Hartley, S. (2018). Project Management. Sydney: Allen & Unwin.

HERALD, Y. (2021). *Union ramping up strike action* [Online]. Fremantle Herald Interactive. Available:

https://heraldonlinejournal.com/2021/03/25/union-ramping-up-strike-action/ [Accessed 18 March 2023].

HERALD, Y. (2021). Square 'in good shape' despite pindan collapse. [Online].

Fremantle Herald Interactive. Available:

https://heraldonlinejournal.com/2021/05/21/square-in-good-shape-despite-pindan-coll apse/[Accessed 18 March 2023].

LOOPERS, R. (2020). *DETAILS OF WALYALUP CIVIC CENTRE FINANCES* [online]. Available:

https://freoview.wordpress.com/2020/07/04/details-of-walyalup-civic-centre-finances/ [Accessed 14 April 2023].

LOOPERS, R. (2021). *IS FREO'S NEW CIVIC CENTRE A DUD?* [online]. Available: https://freoview.wordpress.com/2021/05/09/is-freos-new-civic-centre-a-dud/ [Accessed 09 April 2023].

Loopers, R. (2020). *Details of Walyalup Civic Centre Finances*. [online]. Freo's View. Available:

https://freoview.wordpress.com/2020/07/04/details-of-walyalup-civic-centre-finances/ [Accessed 24 March 2023]. Martins. (2023). What is stakeholder analysis and why is it important? [online]. Available: https://asana.com/resources/project-stakeholder [Accessed 18 March 2023].

Project Management Institute. (2013). *PMBOK Guide*. 5th ed. s.l.:Wiley Online Library.

ROBINSON, D. (2022). *Rusting on their laurels*. [online]. Fremantle Herald Interactive. Available: https://heraldonlinejournal.com/2022/10/07/letters-8-10-22/ [Accessed 09 April 2023].

Tverberg. G. (2016). Intermittent Renewables Can't Favorably Transform Grid Electricity. [Online]. Available:

https://ourfiniteworld.com/2016/08/31/intermittent-renewables-cant-favorably-transform-grid-electricity/ [Accessed 10 April 2023].

Vivian, P. (2023). *Walyalup Civic Centre by Kerry Hill Architects*. [online] Available at: https://architectureau.com/articles/walyalup-civic-centre/ [Accessed 25 March 2023].

Walyalup Koort. (2021). Managing Contractor to Oversee Completion of Walyalup Civic Centre. [online]. Available:

http://www.walyalupkoort.com/news-and-updates/managing-contractor-to-oversee-completion-of-walyalup-civic-centre [Accessed 19 March 2023].

6 Agenda and Meeting Minutes

Meeting 1: 6 March 2023

Location	Online (Teams Call)
Date	6 March 2022
Time	7:00pm-7:38pm
Attendance	Aneena Sebastian (AS), Marco Sham (MS), Nikhil Sunil Kumar
	(NSK), Shubo Sun (SS), Yazhen Tian (YT)
Absent	N/A
Minutes Taken By	Yazhen Tian (YT)
Chair	Yazhen Tian (YT)

Agenda Items

- 1. Each person introduces himself/herself
- 2. Determine the weekly meeting time
- 3. Develop a time plan and create a timeline
- 4. Each group member shares the items found

Meeting minutes

Activity	Notes	Action Items
Accept	N/A as this is first meeting	
minutes		
from last		
meeting		
Introductions	- Group members introduce each other (names,	N/A
	majors studied)	
	- Determine the time and format of weekly	
	meetings.	
	- Exchange of searched projects	
Presenting	- Prior to the meeting YT set up a schedule	
Ideas	through the When2meet website where everyone	

could put their free time on the schedule. Determine the best time for the group meeting. YT - created a shared word doc on Teams to support group members in putting items and specific information they found worth studying in the doc. - Each person took turns presenting the project they had found and explaining why they had picked it. AS - presents the Queen Victoria Street- Swan River Crossing Project - The project was proposed by Main Roads Western Australia, and it includes the construction of new roads and rail bridges, upgradation of existing rail bridges and demolition of existing traffic bridge in Fremantle. The reasons: 1. It is a government project and a lot of free information and project reports are available online. 2. The project is at the delivery stage right now with forecasted cost less than 5% over the current approved budget and forecasted delivery less than 3 months over the approved time. MS - Brookton Highway project -The Highway project was proposed by main roads Australia as a strategy to make Brookton

highway safer and smoother. The road shoulders

along Brookton Highway were widened to 10 metres between Karragullen and Brookton. The reasons: 1. It is a government project and a lot of free information and project reports are available online. **NSK** - presents the Onslow power project - It is Australia's most extensive Distributed Energy Resources Management System (DERMS), and it is world's first achievement. SS - presents the project of Chevron Australia - It is a newly finished project in Perth which just finish the construction. YT - presents The Walyalup Civic Centre & YT to investigate Arrowsmith Hydrogen Project the Walyalup - The Walyalup Civic Centre, designed by Civic Centre Fremantle firm Kerry Hill Architects, is a project in more landmark in Fremantle. The Walyalup Civic detail to determine Centre is a government-funded community public if there is enough service community that combines a library, information to information and customer service centre, meeting conduct rooms and an exhibition hall. assignment The reasons: 1. The Walyalup Civic Centre is a government project and much of the information is available to the public. It can provide us with a lot of valuable data and information, which will facilitate our further research. 2. The architecture of The Walyalup Civic Centre

	is very distinctive. It mixes history and modernity	
	very well.	
	3. During our investigation, we found that this	
	building was changed to different construction	
	companies during the construction process. There	
	should be a lot of points worthy of our research in	
	this.	
Decide on top	Based on the information available and the	
Five projects	interest of the group members, the following five	
	projects were selected (ranked in order of priority)	
	- The Walyalup Civic Centre	
	- Arrowsmith Hydrogen Project	
	- Brookton Highway project	
	- Chevron Tower project	
	- Onslow Power Project	
	- Queen Victoria Street-Swan River Crossing	
	Project	
Discussion of	- Regular team meetings will be held every	
regular team	Monday at 8pm.	
meetings	- YT develop the time plan and timeline	
	- Minutes will be taken by team members on a	
	rotating basis, in alphabetical order.	

Summary of Action Items

Action Items	Owner(s)	Deadline	Status
Further investigate the Walyalup Civic	All	9 March 2023	In Progress
Centre project			
Set timetable and weekly meeting time	All	6 March 2023	Complete
Continue to search for projects suitable	All	9 March 2023	In Progress

as research subjects			
----------------------	--	--	--

Post-Meeting Reflections

1. Did the meeting achieve its objectives?

Yes.

2. Was it successful in all aspects?

Yes, we made a schedule and a time plan.

3. Were there any matters which could have been handled better?

We would like the group members to be able to respond to messages from the group.

Meeting Approval	Aneena Sebastian, Marco Sham, Nikhil Sunil Kumar, Shubo Sun,
	Yazhen Tian

Next Meeting Details

Date	9 March 2023
Venue	Online (Teams Call)
Start Time	8:00 pm
Minutes Writer	Shubo Sun

Meeting 2: 9 March 2023

Location	Online (Teams Call)
Date	9 March 2023
Time	8:00pm-9:17pm
Attendance	Aneena Sebastian (AS), Marco Sham (MS), Nikhil Sunil Kumar
	(NSK), Shubo Sun (SS), Yazhen Tian (YT)
Absent	N/A
Minutes Taken By	Shubo Sun (SS)
Chair	Marco Sham (MS)

Agenda Items

- 1. Discuss together the parts of Section A that need attention.
- 2. Identify the content of meeting minutes.

Previous Action Items

Action Items	Owner(s)	Deadline	Status
Further investigate the	All	9 March 2023	Compeleted
Walyalup Civic Centre project			
Continue to search for projects	All	9 March 2023	Compeleted
suitable as research subjects			

Meeting minutes

Activity	Notes	Action Items
Accept	Accepted by all.	
minutes		
from last		
Discuss what	- We think that Section A should contain mainly an	
need include in	introduction to the project.	
Section A	The following sections are needed:	
	- Introduction	
	 Project background 	
	- Key Stakeholders	
	- Issues/Competencies Relevant to	
	Further Discussion	
Identify the	- Identify the need for a fixed number of minutes to	
content of	be filled in for each meeting minutesx. Make sure	
meeting	each member knows what the meeting minutes need	
minutes.	to contain.	
	- Minutes need to contain information about each	
	meeting, agenda items, previous action items,	

meeting specifics, action item summaries, post-meeting reflections and details of the next meeting.	
YT - A template for meeting minutes was created. All	
subsequent meeting minutes are filled in according to the template.	

Summary of Action Items

Action Items	Owner(s)	Deadline	Status
A template for meeting	YT	9 March 2023	Compeleted
minutes			
Gather as much information	All	13 March 2023	In process
as you can about the WCC			
project			

Post-Meeting Reflections

1. Did the meeting achieve its objectives?

Yes.

2. Was it successful in all aspects?

All previous tasks were completed.

3. Were there any matters which could have been handled better?

We could only see a small number of group members struggling to complete the tasks set. Some panelists allocated too little time to this report.

Meeting Approval	Aneena Sebastian, Marco Sham, Nikhil Sunil Kumar, Shubo Sun,	
	Yazhen Tian	

Next Meeting Details

Date	13 March 2023
------	---------------

Venue	Face2Face
Start Time	5:00 pm
Minutes Writer	Yazhen Tian

Meeting 3: 15 March 2023

Location	Face2Face
Date	15 March 2023
Time	5:40pm-6:30pm
Attendance	Aneena Sebastian (AS), Marco Sham (MS), Nikhil Sunil Kumar
	(NSK), Shubo Sun (SS), Yazhen Tian (YT)
Absent	Aneena Sebastian (AS)
Minutes Taken By	Yazhen Tian (YT)
Chair	Marco Sham (MS)

Agenda Items

- 1. Share what information we have found about the WCC project.
 - 2. Organise a list of questions to ask in meetings with Ryan.
 - 3. Assign tasks to the content of Section A.

Previous Action Items

Action Items	Owner(s)	Deadline	Status
Gather as much information	All	15 March 2023	Completed
as you can about the WCC			
project			

Meeting minutes

Activity	Notes	Action Items
Accept	Accepted by all.	
minutes		
from last		

	, , , , , , , , , , , , , , , , , , ,	
Share what	- MS and YT found information about the city of	
information	Fremantle's meetings. There is a lot of information	
about the WCC	in there about the WCC projected.	
project		
Organise a list	YT - Collated a word document. Put together a list	
of questions to	of questions to ask Ryan, the KHA manager, for the	
ask Ryan	meeting afterwards.	
	YT - Email Ryan a list of questions in advance so	
	that Ryan knows what we want to ask in advance.	
	- Set up a time and place for the	
	meeting with Ryan and make sure Ryan and	
	the group are available at the time of the	
	meeting.	
Assign tasks to	We take your own choice of sections of interest on	
the content of	a first-come, first-served basis.	
Section A	- Introduction: YT	
	- Project background: YT & NSK	
	- Key Stakeholders: SS	
	- Issues/Competencies Relevant to	
	Further Discussion: MS & AS	
-		

Summary of Action Items

Action Items	Owner(s)	Deadline	Status
A list of questions to ask Ryan	All	15 March 2023	Compeleted
Finish draft section of Section A	All	20 March 2023	In Process
Determine the time and place of the	YT	15 March 2023	Compeleted
meeting			

Post-Meeting Reflections

1. Did the meeting achieve its objectives?

Yes.

2. Was it successful in all aspects?

We were able to deepen our understanding of the WCC project by collating the questions we needed to ask Ryan.

3. Were there any matters which could have been handled better?

The group members were not very motivated and needed to be supervised to complete their tasks.

Meeting Approval	Aneena Sebastian, Marco Sham, Nikhil Sunil Kumar, Shubo Sun,
	Yazhen Tian

Next Meeting Details

Date	20 March 2023
Venue	Face2Face
Start Time	12:00 pm
Minutes Writer	Marco Sham

Meeting 4: 20 March 2023

Location	Face2Face - Ezone meeting pod	
Date	20 March 2023	
Time	12:00 pm – 2:00 pm	
Attendance	Aneena Sebastian (AS), Marco Sham (MS), Nikhil Sunil Kumar	
	(NSK), Shubo Sun (SS), Yazhen Tian (YT)	
Absent	N/A	
Minutes Taken By	Marco Sham (MS)	
Chair	Marco Sham (MS)	

Agenda Items

1. Determine the meeting with Ryan from Kerry Hill Architects

- 2. Finish draft section of Part A by Wednesday/Thurs
- 3. Write questions for Ryan regarding the construction project of the WCC

Previous Action Items

Action Items	Owner(s)	Deadline	Status
Question with Ryan	All	22 March 2023	Completed
Finish draft section of Section A	All	24 March 2023	Incomplete
Determine meeting with Ryan	All	20 March 2023	Completed

Meeting minutes

Activity	Notes	Action Items
Accept	Accepted by all.	
minutes		
from last		
Discussion on	MS - has compiled the questions discussed at the	Completed
project	meeting with Ryan, the manager of KHA, and	
timeline	posted them to the group. The questions that Ryan	
	answered were explained to those who were not at	
	the meeting.	
	- Members are occupy with other units and will	
	require more time to complete Section A.	
	- More time is approved to finish section A.	

Summary of Action Items

Action Items	Owner(s)	Deadline	Status
Split up section B	A11	25 March 2023	Completed
Finish section A	A11	3 April 2023	Completed
Writing Section B	All	9 April 2023	In progress

Post-Meeting Reflections

1. Did the meeting achieve its objectives?	
Yes.	

2. Was it successful in all aspects?

We had a successful meeting with KHA's project manager and a tour of the WCC project. Having done the preliminary research was the start of a successful report.

3. Were there any matters which could have been handled better?

Only three members met with the KHA manager and also needed to individually tell the two members who did not attend what our meeting was about. This delayed a lot of effective time.

Meeting Approval	Aneena Sebastian, Marco Sham, Nikhil Sunil Kumar, Shubo Sun,
	Yazhen Tian

Next Meeting Details

Date	27 March 2023
Venue	Face2Face
Start Time	1:00 pm
Minutes Writer	Aneena Sebastian

Meeting 5: 27 March 2023

Location	Face2Face - Ezone meeting pod	
Date	27 March 2023	
Time	1:00 pm - 3:00 pm	
Attendance	Aneena Sebastian (AS), Marco Sham (MS), Nikhil Sunil Kumar	
	(NSK), Shubo Sun (SS), Yazhen Tian (YT)	
Absent	N/A	
Minutes Taken By	Aneena Sebastian (AS)	
Chair	Marco Sham (MS)	

Agenda Items

- 1. Finish draft section of section A by Monday
- 2. Start writing section B next week
- 3. Discuss on the Answers given by Ryan in the meeting

Previous Action Items

Action Items	Owner(s)	Deadline	Status
Meeting with Ryan	All	27 March 2023	Complete
Finish section A	All	27 March2023	In progress
Write questions before meeting	All	26 March 2023	Complete
Ryan			

Meeting minutes

Activity	Notes	Action Items
Accept	Accepted by all	
minutes		
from last		
	YT - produced the report cover and table of	Completed
	contents.	
	- Since some could not finish section A as	
	previously decided, a new deadline was set, and all	
	team members decided that we should complete	
the final draft of section A by 3 rd April.		
	- Once section A is done, we should start writing	
	section B.	
	- Decided on the split up of section B.	
	Introduction - YT	
Conceptualization - SS		
Planning - MS & YT		
Execution – AS		
	Finalization-NSK	
Discussion on	- YT, MS, SS explained the answers given by Ryan	N/A
answers	in the meeting to NSK and AS who could not join	
given by	them.	

Ryan	MS - prepared a file and put down the answers	
	there for everyone to refer.	

Summary of Action Items

Action Items	Owner(s)	Deadline	Status
Split up section B	A11	25 March 2023	Complete
Finish section A	A11	3 April 2023	Complete
Writing Section B	All	9 April 2023	In progress

Post-Meeting Reflections

1. Did the meeting achieve its objectives?

Yes

2. Was it successful in all aspects?

No, we couldn't complete section B as planned

3. Were there any matters which could have been handled better?

We need to ensure that we are meeting the deadlines

Meeting Approval	Aneena Sebastian, Marco Sham, Nikhil Sunil Kumar, Shubo Sun,	
	Yazhen Tian	

Next Meeting Details

Date	9 April 2023
Venue	Online (Teams Call)
Start Time	8:00 pm
Minutes Writer	Yazhen Tian

Meeting 6: 9 April 2023

Location	Online (Teams Call)
----------	---------------------

Date	9 April 2023								
Time	8:00 pm - 8:50 pm								
Attendance	Aneena Sebastian (AS), Marco Sham (MS), Nikhil Sunil Kumar								
	(NSK), Shubo Sun (SS), Yazhen Tian (YT)								
Absent	N/A								
Minutes Taken By	Yazhen Tian (YZ)								
Chair	Marco Sham (MS)								

Agenda Items

- 1. Check the status of section A, section B and meeting minutes records
- 2. Share the information you have found about the project
- 3. Discuss the problems encountered in writing the report

Previous Action Items

Action Items	Owner(s)	Deadline	Status
Finish section B	All	27 March 2023	Complete
Finish Meeting Minutes	All	27 March2023	In progress

Meeting minutes

Activity	Notes	Action Items
Accept minutes	Accepted by all	
from last		
Check the status	Most of the group completed these parts, but	All previous
of section A,	two did not complete the meeting minutes.	meeting minutes
section B and		must be
meeting minutes		completed before
		the next meeting.
Share the	NSK - He found the publicly available News &	

information	Update for the WCC project. This public					
found about the	information clearly illustrates the project's					
project	expenditure. We have found that many places					
	have different prices in terms of project					
	expenditure. the official information published					
	by the WCC should be the most authoritative.					
	MS - He found the City of Fremantle's public					
	agenda for the WCC project: Agenda-Audit and					
	Risk Management Committee.					
Discuss the	As everyone had not yet sorted out the	The meeting takes				
problems	problems they had encountered, MS decided to	place again the				
encountered in	have another meeting the next day where we	following day.				
writing the	could all focus on presenting the problems and					
report	solve them together.					

Summary of Action Items

Action Items	Owner(s)	Deadline	Status
Finish Meeting Minutes	All	13 April 2023	In progress
Finish section C	All	13 April 2023	In progress
Refinement of section A and B	All	12 April 2023	In progress

Post-Meeting Reflections

1. Did the meeting achieve its objectives?

Yes.

2. Was it successful in all aspects?

Yes. We made a lot of progress with our report.

3. Were there any matters which could have been handled better?

We still need to step up the pace. Set aside 4 days in advance to refine the draft.

Meeting Approval	Aneena Sebastian, Marco Sham, Nikhil Sunil Kumar, Shubo Sun,
	Yazhen Tian

Next Meeting Details

Date	13 April 2023							
Venue	nline (Teams Call)							
Start Time	8:00 pm							
Minutes Writer	Shubo Sun							

7 Team Reflection

This time our group's report is based on the project lifecycle of the WCC project, which is the first time we have conducted research and studies on a real project. This section describes the difficulties and challenges we encountered in this process and how we resolved them step by step.

The biggest difficulty we encountered was the lack of motivation of the team members during the first half of the report. The first half of our report was difficult to unfold. Firstly, the group members' schedules were so full that it was difficult to coordinate the participation of all members in the group's meetings and reports. Our solution was to set a strict schedule and monitor each other's progress towards completion. We followed up on each member's completion in a timely manner. Secondly, none of the members of our group had any experience with real-life projects and no one knew where to start. So we started by unfolding the report separately, with each member responsible for one section. This made the work much less difficult. We went on field trips to the Walyalup Civic Centre and met with the project manager to consult him about the project. Through these methods, many of the initial problems were solved as we got to know the project better. Thirdly, the team members were all introverted and we needed to get to know each other slowly, which took some time. These were the reasons for the slow progress of our initial collaboration. Through our joint efforts, the final project report was presented to the satisfaction of the team members.


Another difficulty was the difficulty in accessing information about the project; the WCC project was a government project and much of the information was confidential. If we needed access to this information, we had to apply to the government and go through various levels of approval. This is very difficult. So, we have been able to obtain this information side-by-side by researching the government's public minutes,

Fremantle news reports and other sources. Everyone in our group worked hard to gather as much information as possible and posted it all to our group share file so that every member of the group could share the information.

We have learnt a lot through the completion of this report. Firstly, group members need to help and encourage each other when they are having difficulties. It is important to remind members when they have not completed a task and to follow up on progress. However, we should not forget that we are a team and the end result requires the efforts of everyone in the team. Secondly, when faced with a task we are not familiar with, ask for advice from someone with experience. Break down a big task into smaller tasks. This makes it easier to achieve one small goal at a time and ultimately complete the big task. Thirdly, when you encounter a problem with your project, you need to reflect on the cause of the problem, find it and solve it. Don't let the problem continue to develop. I believe that if we work together again with the team members, we will be able to work more smoothly.

8 Appendices

Appendices 1 WCC Plans with Legends



Appendices 2 WCC Project Site Plan



Appendices 3: Timeline of WCC Project



Agenda Attachments – Annual General Meeting of Electors Monday 25 February 2019

Timeline:

August 2017

Kings Square renewal begins.

December

City of Fremantle relocated to Freo Oval.

January 2018

Demolition of Myer/Queensgate building.

February

Newman Court closes.

March

Council approved plans to upgrade public spaces in Kings Square.

April

Queensgate carpark refurbishment began (carpark closed for five months).

May/June

Relocation of London Plane trees

Mid 2018

Construction begins on FOMO and new commercial offices.


Appendices 4: Risk Management Matrix

ಕ	5	17	25	ij.	r	ä	ri .	- 3	8	ы		ч	o	te .		te	M	-	ITEM
Project Team / knowledge and experience	Def Staff evaluating	Teratricy delays	Prolongation Costs	NEW: COVID Supply chain dalays, labour shortages.	berwased Cortractor costs	Incressed Contractor costs	Bonds	Project Budgets / Contingencies	Project Bank Account (PBA)	hautence	Health & Safety Management Plan PRIMANCIAL	OSH Management - daily	Building open to weather derings HEALTH & SAVETY	Contractor - work continuity	Contractors - work continuity	Site impacts / adjacent works	Work Stoppinge	SULDING / PHYSICAL Building (Urmanned) Security and protection	HISK / OPPORTUNTY EVENT
Loss of the sile project learn (Pinder) will coate a aignificual void in project brookedge and contractor realizonal presupprised Coordinate, Significant trake, costs and didays involution.	Colf staff and internal workforce planning had not anticipated active delivery insolvement in the project beyond August 21:	Daruptipon and delays may impact availability of terrancy space and or may jeopodias essociting / attracting new terrants.	The LE will prolong the works on site, this will largithen consulted engagement and extend fees on a pro-rata basis.	Suppliers and contractors costs are increasing and works / delivery. Street areas are increasing. This is parting pressure on works posgram and PC delivery.	The LE with Pinden may break the existing context. If SC's with black have autocontraction / suppliers - the Coff may large delays or revised continition contactors with new laters.	The hold in work activity and delega resulting from the LE may lead to contractors or suppliers. supplying additional charges (e.g., storage or mobitio- mats).	Bood security, access and stally to thew - Bonds are in place for - performance (§ 5% contract value, lepade bonds (§ 51.6m for material supply. Other for agnificant materials / works (Ufb)? ⁹	Cof budget terseira against the cortexted sorts (§ close \$3.0m) remaining cortingercy available (§ close \$5004). Unuare of actual cost to complete	Administrators (EV) fraces the PSA - Coff / Contractors access to funds and payments, solerator monies and April payment panding.	Works Insurance covered as part of the Pinden contracted work. Cover curve at liquidation. Building uninsured.	No formal / adopted H&S Management in place	No minedate or elerim also amengements in place	Building open with key elevations not complete - topode not installed.	Contractors move to other works - Coff unable to re emprys or fixed delays or cost increases / amended TAC's.	Key personnel and contractors left mid-ecolor. project progress, detail and knowledge unavailable.	Site overlaps and interfaces with MC group - Nesemen Court / William St and High Street works - ongoing.	Works abrupily stopped / Contractors left site - encentainty on perventitip materials and equipment	Site unmanaged - building and materials left unsecure	MISK / MISLE
34-May-21	24-May-21	34-May-21	24-May-21	13-06-21	34-May-21	24-May-21	24-May-21	24-May-21	34-May-21	24-May-21	34-May-21	24-May-21	25-May-21	34-May-21	34-May-25	24-May-21	24-May-21	24-May-21	DATE
	N	u	ш	ы	ш	ш				u		4			4	u	u	A	Consequence (5.2,3,4,5)
u	w	u _c	*	u	u	*	u	a.	эн		*		u		*	ы		*	Likelhood (1,2,3,4,5)
ы		10	ß	0.	10	Ñ	ū	ő	ñ	B	ñ	6	8	iš.	16	0	ij.	6	Assessment 3
	*	*			×					7		7				*		*	Initial Risk Rating (E,HM,L)
Celf to immediate most to enlarge the key Pinden sits project team, Raida serviers in terms of sidef selection, commission makes running very not- numerous approaches for staff occurry.	brinstructure Managers have reviewed workload and optided their respective workload planting (and PV works programming).	Cof are actively lastisting with the prospective tensets. These areas of the building will be prioritised for clearing and access to minimize potential tensercy delay.	the Colf have engaged with the relevant consultants in grotongation costs. These are agreed to be applied on a pro-bita basis but will reflect activity I work real fluctuators.	Project hum actively liabiling with contractors and suppliers and exchening programs / delivery lead financels.	Active finisher with contractors ongoing. Batch but arons are low risk - marky supply and onto for agreed works.	Active listaion with contentions ongoing. Novelon deeds have secured - the majority of costs under wateing Finder 1962's, (patch one contractors). Eatch too are unsecure agreements - see below.	Cof immediately moved to cash in all released imazenos bonds to polect against eachs performance and materials.	Physici karn rekewing works and coals to compiles. If di coal review swarcas anderway, All coal implications to be held against the resummes bonds.	All leasing with EY and CBA in Willing the auspensors of the PBA. All committees just to date. Admitted, Marchell Marchell dates certified but not processed through the PBA for payment—only \$200 discussed to Perchan in the April dates. Colf to compiler deset payment to committee for April.	EY (via LGIS) that the a 130 June 21. Coff later oprists new cover for the	Coff and project Team nevieward the Pinclain CRS in management plain and populated in Management and Coff inquirements. Consultate site I plain review conducted. Worksade inspection (multima) taken place - no issues or concerns assed. Documents inviewed by Coff OSH Team Leader.	like unoccupied - Interim menagement energements and security implemented and project learn established and create with updated / agreed plan.	Officers seek Council approach to engage project subcontentions as sole explains the resolute death and tribitated appreciates and tribitate of templates the resolute death and tribitated appreciates and tribitate or subcontentions are proposed to the results (NOTE Council and NOTE COUNCIL a	Coff extractionity entity of the man Pirabat project have, the learn activaty engaged with cost active and restrictions dissign, if these up common observations from the Coff and a costing provided to produce annual reason and from the Coff and a cost of the cost of	Cell actively engaged with the Pinder project learn, all relevant documents colleged from site – including contractor deads / T&Ch, warrantee and progress claims.	Coff laised with MG and agnisid work also boundaries and interim management arrangements.	Colf actively engaged Lawyers and baland with EV. Colf assessed progress documentation / materials paid for, ouslanding / in transit and on site. City to take possession of site.	hoseased security on also, Also adoled addditional CCTV and requested dialry also presence.	MITIGATION STRATEGY
8	8 8	E	8	8	8	8	Ca.	£	£	g	8	8	8	g.	8	g.	C.	8	OWNER
, P.	PD, PT.	PD, PT.	PD, PT.	PD, PT.	PD, PT.	PD, PT.	PD, PT.	PD, PT.	PD, PT.	PD, PT.	TL PT	75, 05H	PD, PT	PD, PT	PD, PT	PD, PT	PD, PT	PD, PT	RESPONSIBLE
1-Nov-21	1-Nov-21	1-Dec-22	1-Nov-21	1-Dec-22	1-Nov-21	1-Nov-21	28-May-21	1-Dec-22	31-Aug-21	38-Jun-21	M-Jun-21	1-Nov-21	31-Aug-21	15-Jun-21	28-May-21	25-May-21	dere	25-May-21	TARGET DATE
chased	classed	grappe	dassi	Buplico	dass	deset	doed	priopro	dosed	di E	closed	dawd	closed	dosed	dosed	dased	dased	closed	STATUS
-	-	N		N		-	-		-		-	-	-		2	10	-	-	Control Effectiveness (3.2.3.4.5)
9	1,000	168	80%	99	89	1000	80%	80%	80%	99	9	80%	20	20%	100	20%	80%	N256	Per centage Reduction
-	12	3.6	24	2.4	ű	2.4	2.4	3.2	24	N	12	ı,	10	12	3.2	12	2.4	3.2	Assessment 2
· ·	r	r.	-	P	F	-	e.	e	r	-	-		-	-	r.	-	۲	-	Residual Risk Rating (E.H.M.L)
Corsiduction works complete - project learn freshed.	Construction works complete - defects managed arough PM.	Nearman Court lanancies agreed - 16 out staged in consultation with terrets. Other awas under negotiation/seating proposals. (Separate fil-out budget for terrancies).	Costs backed against PC - achieved November 2001.	Regular proschive lesson underway across all areas. Some delays are occuring for contractor anellability for defect rectification. (minor items).	As slove - all Balch 2 contractors are secured and active.	The project learn have secured all contractors to complete the contracted works (on original Photae costs), continuity and price security.	All bonds secured by the CoF 26-May-21	Cast is complete actively monitored through project in harm OS and project Merapyra - Ademia harm of declarated to include goods and commitments (in commitments commitments or wavely review). Current entimeted commitments in outhern ceals in \$400,010,345 (or GST), NS. Bornts cambred (§ \$1.0m.)	PBA suspension that by EY. Coff now have access to main account and the the retention account.	Project Works Cover / Building and 3rd party cover, works compensation in place.	sea done.	PC/Decupancy Certificate achieved - Building occupied.	Building now wind and weather light.	All death / T&C's, warrantes by of claims secured.	Key personnel secured / relatived by Coff.	x defined and overlaps / control and / actively monitored by Project		Normal abs management / security emergements implemented, includes motion detection and temp security carrants.	FURTHER NOTES I OUTCOMES (Vad test * updated from provious regular)
PM learn now manage the building (in-incase).	Defects logged and managed through PM and CDI procure system.	No additional project costs or provisions (mlading to LE) included.	TechChe - New WISS in place with WO's for specific post liquidation events. All coethiconneitments and contractor payments tracked and certified.	CDI Group Maintenance jand defects) system capuring all issues / polentional outstanding works - sateriton/payment hald against completion of all storts.	TechChis - New WBS in place with WO's for apacific poet liquidation awarts. All contribioministrants and contractor payments bracked and certified.	TechOns - New WIBS in place with WO's for specific post liquidation swerts. All costs/commitments and contractor payments tracked and certified.	payment semillance secreted for all performance and fidential (figures) bonds.	TachChe - WBS in place with WC's for specific poel liquidation events. All coshidorate/mark and confractor payments tracked and certified. Remaining draw-down schools produced: Final accounts being collected and reviewed.	Accounts accessed and monitored.	Policies in place - CDI policies (copies) provided:	Project OSH Managament Plan.	Building Managard through FM, warviox leads and Opertainnel Managament plans.	Roding Intehed, all key windows and facades matched and pressure betted.	All contractors re-engaged and active where remaining works.	Project learn on site - leading works.	Updated Site Management Plan / project meeting minutes.	Works programing.	Organiq alte security precautions in place - process & procedures documented as part of the alter management plan.	ENDENCE

Construction of a House 100% \$215,500 1. Internal 2. Foundation 3. External Level 1 45.60% \$86,000 \$46,000 \$83,500 Budget Budget Budget 2.1 Excavate 1.1 Electrical 3.1 Masonry Work Leg Electrical Contractor Labor Crew Masonry Contractor Elements 11.80% Work 16.20% Work Budget \$25,000 Budget \$37,000 Budget \$62,000 1.2 Plumbing 2.2 Steel Erection 3.2 Building Finishes Plumbing Contractor 33.80% 5.8% 14.20% Budget \$61,000 Budget \$9,000 Budget \$21,500

Appendices 5: Work Breakdown Structure

Appendices 6: Evidence of Email Correspondence with KHA Project Manager



Appendices 7: Final Cost of the WCC Project

WCC Forecast to Complete (*whole)	\$46,127,340.29
PSUM Deductions & Variation Adjustments	-\$199,304.40
William Street Verge Works (Carriageway kerbs/drainage)	-\$30,552.50
Town Hall basement – waterproof tanking (Western Power Area)	-\$47,486.86
Tenancy Works (Visitor Centre)	-\$239,864.41
Total Forecast (WCC – contract scope)	\$45,610,132.12

Appendices 8 Interview Questions

1. What difficulties did you encounter while working on this project?

i. Bilder issue.

Because Pindan went bankrupt, a new builder had to be replaced. This delayed the process.

ii. The Covid problem.

Supply chain issues: many building materials come from overseas or Brisbane. The Covid caused delays in the arrival of materials. So they had no choice but to do the interior renovation first. This also led to increased costs. Contractors need to follow covid rules. Was allowed to continue construction.

Worker issues: The Covid has resulted in many workers needing to be isolated at home, which has severely impacted on the work schedule.

2. What is the timeline of the WCC project? Can you please tell us the time use lifecycle (conceptualisation, planning, development, and finalisation)?

Conceptualisation stage started at 2014.

Planning stage started at 2016.

Development stage started at 2018.

Finalisation stage started at 2020 and finished in November 2021.

3. Are there any memorable things in each stage?

Designing stage: need to obtain from the city (the client).

- 1) A demolition permits
- 2) A building permits. Both are obtained through the presentation.

4. Project Benefits and Goals

Reviving Kings Square as the centre of Fremantle.

5. How were the construction and design issues handled?

Contracts:

Contracts are drafted and purposed by a third-party company called TPM (Total Project Management) company acts as a communication between the building contractor.

Design:

Design issues are inspected by the design team and the contractor and is discussed in a fortnight meeting?

6. Risk Management

Risks are assessed throughout the project and reported by all contributing parties that were onsite. Mitigation actions are often done by the main contractor of the project (Pindan). Mitigation actions are often not reported in the performance review of the project.

7. Budget and Cost Management

Cost of Budget is 45 million: not over budget.

8. The Heritage consultant, protection of cultural heritage.

Design trouble:

Preserving the lime wall in the lobby of the civil centre while updating and following the building restrictions and safety laws, such as fire codes.

Engineering:

The contractor does the engineering work making the design buildable.